DIVISION 7 - THERMAL AND MOISTURE PROTECTION

1. ENERGY COMPLIANCE

FIXED WINDOWS (GLASS) SHALL BE SEALED TO LIMIT AIR INFILTRATION.

HOLLOW METAL OR SOLID CORE WOOD DOORS: PROVIDE VINYL OR SHEET METAL WEATHER SEAL AT HEAD, JAMB AND SILL AT ALL EXTERIOR DOORS.

EXTERIOR STORE FONT HINGED DOORS: PROVIDE VINYL SEAL AT SILL AND CONTINUOUS PILE WEATHER-STRIP VERTICALLY AND AT TOP RAILS.

OPEN EXTERIOR JOINTS AROUND WINDOW AND DOOR FRAMES, BETWEEN WALLS AND FOUNDATION, BETWEEN WALLS AND ROOF, BETWEEN WALL PANELS, AT PENETRATION OF UTILITIES THROUGH THE ENVELOPE, SHALL BE SEALED CAULKED OR WEATHER-STRIPPED TO LIMIT AIR LEAKAGE.

2. BUILDING INSULATION

WORK INCLUDED: FURNISH AND INSTALL RIGID, THERMAL BATT, AND SOUND BATT INSULATION.

ROOF INSULATION: RIGID POLY-ISO INSULATION: R30 MINIMUM

BATT INSULATION: R-19, R-13, R-11 AS SHOWN ON PLANS, KRAFT FACED WITH STAPLING FLANGE FOR WOOD STUD WALL CONSTRUCTION, FOIL REINFORCED KRAFT FACING (FRK) WITH STAPLING FLANGE FOR WOOD STUD APPLICATION IN ATTIC AREAS (FS-25 WITH FLAME SPREAD OF 25). AS MANUFACTURED BY OWENS/CORNING FIBERGLASS, OR EQUAL.

SOUND BATT INSULATION: NON-COMBUSTIBLE MINERAL FIBERGLASS BATTS WITH MINIMUM 3 1/2" THICKNESS.

VAPOR BARRIER: TRANSLUCENT POLYETHYLENE FILM FOR USE IN ABOVE GRADE BUILDING CONSTRUCTION, 6 MIL MINIMUM THICKNESS. (INTERIOR ONLY)

3. MEMBRANE ROOFING

MATERIALS: PROVIDE DURO-LAST ROOFING AND BASE FLASHING AS MANUFACTURED BY DURO-LAST ROOFING SYSTEMS. PRODUCT AND INSTALLATION SHALL CONFORM TO MANUFACTURERS SPECIFICATION AND 2006 IBC CHAPTER 15 & TABLE 1507.10.2. REFER TO ROOF PLAN FOR ADDITIONAL INFORMATION.

INSTALLATION: ROOFING SHALL BE INSTALLED BY MANUFACTURER CERTIFIED INSTALLER. ROOFING SHALL BE INSTALLED OVER WOOD DECK OR INSULATED DECK, WHERE APPLICABLE, IN STRICT ACCORDANCE WITH THE MANUFACTURER'S LATEST RECOMMENDATIONS. PRIME ALL METAL FLASHING, ETC. THAT SHALL BE IN CONTACT WITH ROOFING MATERIALS.

WARRANTY: GENERAL CONTRACTOR SHALL FURNISH A FIFTEEN (15) YEAR, NO DOLLAR LIMIT (NDL), WARRANTY FOR THIS INSTALLATION.

4. FLASHING AND SHEET METAL

FURNISH AND INSTALL ALL FLASHING, SHEET METAL, PITCH POCKET PANS AND SCUPPERS NOT SPECIFICALLY DESCRIBED IN OTHER SECTIONS OF THESE SPECIFICATIONS, BUT REQUIRED TO PREVENT WATER PENETRATION THROUGH EXTERIOR BUILDING SHELL, INCLUDING FLASHING, CAPS, AND ROOF EQUIPMENT PLATFORM COVERS.

COMPLY WITH APPLICABLE RECOMMENDATIONS AND DETAILS OF THE "ARCHITECTURAL SHEET METAL MANUAL", BY SHEET METAL AND AIR CONDITIONING CONTRACTOR'S NATIONAL ASSOCIATION (SMACNA).

INSTALL SHEET METAL OVER A LAYER OF ROOFING FELT.

GALVANIZED IRON: SHEET METAL OR IRON SHALL BE A STANDARD BRAND OF OPEN-HEARTH, COPPER-BEARING STEEL, COPPER-MOLYBDENUM IRON, OR PURE IRON SHEETS. USE 24 GAUGE MINIMUM UNLESS OTHERWISE CALLED FOR ON THE DRAWINGS.

ZINC COATING: ALL GALVANIZED SHEETS SHALL HAVE A ZINC COATING APPLIED BY HOT-DIP PROCESS TO ALL SURFACES. ZINC COATING SHALL WEIGH NOT LESS THAN 1 1/4 OUNCES PER SQ. FT. NOR MORE THAN 1 1/2 OUNCES PER SQ. FT. OF SURFACES COVERED AND SHALL CONFORM WITH ASTM A-93.

5. ROOF ACCESSORIES

THE WORK OF THIS SECTION INCLUDES THE PROVIDING AND INSTALLING OF ACCESSORIES TO BE INSTALLED ON THE ROOF AND FLASHED TO PROVIDE A WATERTIGHT INSTALLATION.

ROOF HATCH: BILCO, TYPE "S-20", 2'-6" X 3'-0", GALVANIZED, BONDED FOR PAINTING.

6. CAULKING & SEALANTS

GENERAL BUILDING APPLICATIONS: FOR JOINTS WHERE MOVEMENT IS ANTICIPATED, USE A.C. HORN HORNFLEX (POLYSULFIDE) ONE COMPONENT SYSTEM IN THE COLOR WHICH MOST CLOSELY MATCHES THE ADJACENT SURFACES. SEALANT TO HAVE A SHORE "A" HARDNESS OF 20 TO 30.

FOR DRY JOINTS BETWEEN DISSIMILAR MATERIALS WHERE LITTLE MOVEMENT IS ANTICIPATED, USE A.C. HORN HORNSEAL ELASTOMERIC CAULK (BUTYL RUBBER) ONE COMPONENT SYSTEM IN THE COLOR WHICH MOST CLOSELY MATCHES ADJACENT SURFACES.

FOR GLAZING AND KITCHEN APPLICATIONS:
GENERAL ELECTRIC SILICONE CONSTRUCTION 1200 SEALANT.

FOR SHEET METAL FLASHING AND COPING:
GENERAL ELECTRIC SILPRUF SILICONE WEATHER PROOFING SEALANT.

THE GENERAL CONTRACTOR SHALL INCLUDE IN HIS WORK THE FOLLOWING: AFTER ALL EQUIPMENT AND WALL MATERIALS ARE INSTALLED, ALL JOINTS TO WALLS AND BASES SHALL BE SEALED WITH SILICONE SEALANT.

ALL INSIDE VERTICAL CERAMIC TILE CORNERS SHALL RECEIVE A TOOLED BEAD OF SILICONE SEALANT.

7. EIFS (EXTERIOR INSULATION AND FINISH SYSTEM)

WORK INCLUDED:
ALL MATERIALS AND INSTALLATION OF AN EIFS SYSTEM.

DESIGN REQUIREMENTS: CONFORM IN ALL RESPECTS TO MANUFACTURER'S SPECIFICATIONS FOR MATERIALS AND INSTALLATION PER STO THERM SPECIFICATION FOR STO THERM E100 ESSENCE SYSTEM

DRYVIT MAY BE SUBSTITUTED AS AN ALTERNATE EIFS MANUFACTURER IF APPROVED IN WRITING BY PANDA EXPRESS

MEET ALL LOCAL BUILDING CODE REQUIREMENTS.

MOISTURE CONTROL: PREVENT THE ACCUMULATION OF WATER BEHIND THE EIFS SYSTEM, EITHER BY CONDENSATION OR LEAKAGE THROUGH THE WALL CONSTRUCTION, IN THE DESIGN AND DETAILING OF THE WALL ASSEMBLY. CONFORM WITH ALL DETAILS OF MANUFACTURER'S SPECIFICATIONS.

IMPACT RESISTANCE: PROVIDE ULTRA-HIGH IMPACT RESISTANCE TO A MINIMUM HEIGHT OF 6'-0" ABOVE FINISHED GRADE AT ALL AREAS ACCESSIBLE TO PEDESTRIAN TRAFFIC AND OTHER AREAS EXPOSED TO ABNORMAL STRESS OR IMPACT. INDICATE THE AREAS WITH IMPACT RESISTANCE OTHER THAN "STANDARD" ON CONTRACT DRAWINGS.

COLOR SELECTION: AS SELECTED BY PANDA FROM MANUFACTURER'S STANDARD COLORS.

7. JOINTS: PER MANUFACTURER'S SPECIFICATION

8. GRADE CONDITION: DO NOT INSTALL EIFS BELOW GRADE.

9. PROJECTING ARCHITECTURAL FEATURES AND REVEALS: ALL TRIM AND PROJECTING ARCHITECTURAL FEATURES MUST HAVE A MINIMUM 1:2 SLOPE ALONG THEIR TOP SURFACE ALL HORIZONTAL REVEALS MUST HAVE A MINIMUM 1:2 SLOPE ALONG THEIR BOTTOM SURFACE INCREASE SLOPE FOR NORTHERN CLIMATES TO PREVENT ACCUMULATION OF ICE/SNOW AND WATER ON SURFACE WHERE TRIM FEATURE OR BOTTOM SURFACE OF REVEAL PROJECTS MORE THAN 2 INCHES FROM THE FACE OF THE EIFS WALL PLANE, PROTECT THE TOP SURFACE WITH WATERPROOF BASE COAT. PERIODIC INSPECTIONS AND INCREASED MAINTENANCE MAY BE REQUIRED TO MAINTAIN SURFACE INTEGRITY OF EIFS ON WEATHER EXPOSED SLOPED SURFACES.

10. INSULATION THICKNESS: MINIMUM EPS INSULATION THICKNESS IS 1 1/2 INCHES.

11. FIRE PROTECTION: REFER TO MANUFACTURER'S APPLICABLE CODE COMPLIANCE REPORT FOR LIMITATIONS THAT MAY APPLY.

C. QUALITY ASSURANCE:
1. MANUFACTURER REQUIREMENTS: MEMBER IN GOOD STANDING OF THE EIFS INDUSTRY MEMBERS ASSOCIATION, AND (EIMA). SYSTEM MANUFACTURER FOR A MINIMUM OF TWENTY (25) YEARS, AND MANUFACTURING FACILITIES ISO 9001-2000 CERTIFIED QUALITY SYSTEM.

2. CONTRACTOR REQUIREMENTS: ENGAGED IN APPLICATION OF EIFS FOR A MINIMUM OF THREE (3) YEARS; AND EMPLOY SKILLED MECHANICS WHO ARE EXPERIENCED AND KNOWLEDGEABLE IN EIFS APPLICATION; AND DEMONSTRATE SUCCESSFUL COMPLETION OF MINIMUM OF THREE (3) PROJECTS OF SIMILAR SIZE AND COMPLEXITY TO THE SPECIFIED PROJECT.

3. INSULATION BOARD MANUFACTURER REQUIREMENTS: RECOGNIZED BY STO AS CAPABLE OF PRODUCING INSULATION BOARD; AND LISTED BY AN APPROVED AGENCY. LABEL INSULATION BOARD WITH INFORMATION REQUIRED BY STO, THE APPROVED LISTING AGENCY AND THE APPLICABLE BUILDING CODE.

4. INSPECTIONS: PROVIDE INDEPENDENT THIRD PARTY INSPECTION WHERE REQUIRED BY CODE OR CONTRACT DOCUMENTS CONDUCT INSPECTIONS IN ACCORDANCE WITH CODE REQUIREMENTS AND CONTRACT DOCUMENTS.

D. DELIVERY STORAGE AND HANDLING: AS SPECIFIED BY MANUFACTURER.

E. COORDINATION: THE WORK IN THIS SECTION REQUIRES CLOSE COORDINATION WITH RELATED SECTIONS AND TRADES.
1. PROVIDE SITE GRADING SUCH THAT EIFS TERMINATES ABOVE FINISHED GRADE A MINIMUM OF 6 INCHES (152MM) OR AS REQUIRED BY CODE.

2. PROVIDE PROTECTION OF ROUGH OPENINGS BEFORE INSTALLING WINDOWS, DOORS AND OTHER PENETRATIONS THROUGH THE WALL AND PROVIDE SILL FLASHING.

3. INSTALL WINDOW AND DOOR HEAD FLASHING IMMEDIATELY AFTER WINDOWS AND DOORS ARE INSTALLED.

4. INSTALL DIVERTER FLASHING WHEREVER WATER CAN ENTER THE WALL ASSEMBLY TO DIRECT WATER TO THE EXTERIOR.

5. INSTALL COPINGS AND SEALANT IMMEDIATELY AFTER INSTALLATION OF THE EIFS SYSTEM AND WHEN EIFS COATINGS ARE DRY.

6. ATTACH PENETRATIONS THROUGH EIFS TO STRUCTURAL SUPPORT AND PROVIDE WATER TIGHT SEAL AT PENETRATIONS.

F. PRODUCTS: PROVIDE EIFS SYSTEM AND ACCESSORIES FROM SINGLE SOURCE
1. MANUFACTURER OR APPROVED SUPPLIER. THE FOLLOWING ARE ACCEPTABLE MANUFACTURERS" STO CORP. EIFS; OTHER MANUFACTURER IF APPROVED IN WRITING BY PANDA.

2. INSULATION BOARD: NOMINAL 1.0 LB/FT3 (16 KG/M3) EXPANDED POLYSTYRENE (EPS) INSULATION BOARD IN COMPLIANCE WITH ASTM E2430 AND ASTM C578 TYPE 1 REQUIREMENTS.

3. BASE COAT AS SPECIFIED BY MANUFACTURER.

4. REINFORCING MESHES AS SPECIFIED BY MANUFACTURER.

5. FINISH COAT: STO ESSENCE DPR FINISH, ACRYLIC BASED TEXTURED WALL COATING WITH GRADED MARBLE AGGREGATE AND DIRT PICK-UP RESISTANCE TECHNOLOGY.

G. EXECUTION:
1. INSTALLATION: INSTALL EIFS IN COMPLIANCE WITH MANUFACTURER'S PUBLISHED INSTRUCTIONS.
2. PROTECTION: PROVIDE PROTECTION OF INSTALLED MATERIALS FROM WATER INFILTRATION INTO OR BEHIND THEM. PROVIDE PROTECTION OF INSTALLED MATERIALS FROM DUST, DIRT, PRECIPITATION, FREEZING AND CONTINUOUS HIGH HUMIDITY UNTIL THEY ARE FULLY DRY.

9. VAPOR BARRIER

ALL EXTERIOR SHEATHING SHOWN IN DRAWINGS CALLED OUT TO RECEIVE "WRB" (WATER RESISTIVE BARRIER) OR VAPOR BARRIER SHALL RECEIVE THE FOLLOWING:

MANUFACTURER: STO CORPORATION (www.stocorp.com)

SPECIFICATION: STO GUARD WTH GOLD COAT A1000G

SUBSTITUTIONS: NOT ALLOWED

INSTALLATION: INSTALL PER MANUFACTURER'S INSTRUCTIONS/SPECIFICATIONS

DIVISION 8 - DOORS AND WINDOWS

1. QUALITY ASSURANCE

EXTERIOR WINDOW AND DOORS: WINDOWS AND DOORS INSTALLED IN EXTERIOR WALLS SHALL CONFORM TO THE TESTING AND PERFORMANCE REQUIREMENTS OF SECTION 1714.5*. INSTALLATION.

WINDOW AND DOORS SHALL BE INSTALLED IN ACCORDANCE WITH APPROVED MANUFACTURER'S INSTRUCTIONS. FASTENER SIZE AND SPACING SHALL BE PROVIDED IN SUCH INSTRUCTIONS AND SHALL BE CALCULATED BASED ON MAXIMUM LOADS AND SPACING USED IN THE TESTS*. EXTERIOR WINDOW AND DOOR ASSEMBLIES. THE DESIGN PRESSURE RATING OF EXTERIOR WINDOWS AND DOORS IN BUILDINGS SHALL BE DETERMINED IN ACCORDANCE WITH SECTION 1714.5.1 OR 1714.5.2, EXCEPTION: STRUCTURAL WIND LOAD DESIGN PRESSURES FOR WINDOW UNITS SMALLER THAN THE SIZE TESTED IN ACCORDANCE WITH SECTION 1714.5.1 OR 1714.5.2 SHALL BE PERMITTED TO BE HIGHER THAN THE DESIGN VALUE OF THE TESTED UNIT PROVIDED SUCH HIGHER PRESSURES ARE DETERMINED BY ACCEPTED ENGINEERING ANALYSIS. ALL COMPONENTS OF THE SMALL UNIT SHALL BE THE SAME AS THE TESTED UNIT. WHERE SUCH CALCULATED DESIGN PRESSURES ARE USED, THEY SHALL BE VALIDATED BY AN ADDITIONAL TEST OF THE WINDOW UNIT HAVING THE HIGHEST ALLOWABLE DESIGN PRESSURE.*

EXTERIOR WINDOWS AND GLASS DOORS SHALL BE LABELED AS CONFORMING TO AAMA/NWWDA 101/I.S.2, OR 101/I.S.2/NAFS. THE LABEL SHALL STATE THE NAME OF THE MANUFACTURER, THE APPROVED LABELING AGENCY AND THE PRODUCT DESIGNATION AS SPECIFIED IN AAMA/NWWDA 101/I.S.2 OR 101/I.S.2/NAFS. PRODUCTS TESTED AND LABELED AS CONFORMING TO AAMA/NWWDA 101/I.S.2 OR 101/I.S.2/NAFS SHALL NOT BE SUBJECT TO THE REQUIREMENTS OF SECTIONS 2403.2 AND 2403.3*. EXTERIOR WINDOWS AND DOOR ASSEMBLIES NOT PROVIDED FOR IN SECTION 1714.5.1, EXTERIOR WINDOW AND DOOR ASSEMBLIES SHALL BE TESTED IN ACCORDANCE WITH ASTM E330. EXTERIOR WINDOW AND DOOR ASSEMBLIES CONTAINING GLASS SHALL COMPLY WITH SECTION 2403. THE DESIGN PRESSURE FOR TESTING SHALL BE CALCULATED IN ACCORDANCE WITH CHAPTER 16. EACH ASSEMBLY SHALL BE TESTED FOR 10 SECONDS AT A LOAD EQUAL TO 1.5 TIMES THE DESIGN PRESSURE*.

2. METAL DOORS AND FRAMES

WORK INCLUDED:
FURNISH AND INSTALL METAL DOORS AND DOOR FRAMES AS SHOWN ON THE DRAWINGS AND AS NEEDED FOR A COMPLETE AND PROPER INSTALLATION.

MATERIALS: DOORS AND FRAMES SHALL BE EQUIVALENT TO STEEL CRAFT, LABELED OR NON-LABELED AND SIZE AS INDICATED ON DRAWINGS.

STEEL DOORS SHALL BE FULL-FLUSH DESIGN L-18 (18 GAUGE) REINFORCED FOR FINISH HARDWARE AND WITH BAKED ON PRIME PAINT STEEL FRAMES SHALL BE FURNISHED KNOCKED DOWN, TYPE F-16 (16 GAUGE), MITERED CORNERS SHALL HAVE HEAVY REINFORCEMENTS WITH FOUR TABS FOR SECURING AND INTERLOCKING JAMB TO HEAD. PROPER REINFORCEMENT AND CUT-OUT FOR FINISH HARDWARE. FRAMES SUPPLIED WITH SUITABLE JAMB AND BASE ANCHORS, RUBBER BUMPERS AND PRIME PAINTED.

3. WOOD DOORS

PROVIDE AND INSTALL STANDARD SOLID-CORE, FLUSH WOOD DOORS.
FACE VENEER: REFER TO COLOR AND DOOR SCHEDULES FOR LIST OF DOORS TO RECEIVE SCHEDULED FINISHES.

SOLID CORE: MAT FORMED WOOD PARTICLE BOARD, TYPE 1, DENSITY, CLASS 1, COMMERCIAL STANDARD CS236-66, AS MANUFACTURER, BY U.S. PLYWOOD, GENERAL VENEER OR WEYERHAUSER.

DOORS SHALL BE MANUFACTURED PER MILL WORK STANDARDS OF THE ARCHITECTURAL WOODWORK INSTITUTE (AWI) FOR PREMIUM GRADE.

EDGE BANDING:
PAINTED FINISH: MILL OPTION
STAINED FINISH: MATCH FACE VENEER.

CUTOUTS FOR GLAZING OR LOUVERS SHALL HAVE HARDWOOD FRAMES AND STOPS.

ADHESIVES: CONFORM TO CS 35 TYPE II, FOR INTERIOR DOORS AND TYPE I FOR EXTERIOR DOORS.

DOORS TO HAVE METAL LOUVERS AS INDICATED ON THE DRAWINGS SHALL BE 24 GAUGE WITH CHEVRON TYPE BLADES WITH FREE AIR 50% TOTAL AREA AND BE PRIME PAINTED.

PRE-FIT DOORS AT FACTORY WITH CLEARANCES OF 1/8" AT EACH VERTICAL EDGE AND AT TOP, 1/2" AT BOTTOM, AND 1/8" IN 2" BEVEL AT LOCK EDGE, 3/8" CLEARANCE ABOVE FLOOR WITHOUT THRESHOLD, 1/2" ABOVE FLOOR WITH THRESHOLD.

INSTALL DOORS TO COMPLY WITH MANUFACTURER'S INSTRUCTIONS. FIT DOORS TO FRAMES WITH UNIFORM CLEARANCE AND BEVELS. MACHINE DOORS FOR HARDWARE, IF REQUIRED. REFINISH OR REPLACE DOORS DAMAGED DURING INSTALLATION.

4. FINISH HARDWARE

SECURITY NOTES - SWINGING DOORS:
ALL PIN-TYPE HINGES WHICH ARE ACCESSIBLE FROM OUTSIDE THE SECURED AREA WHEN THE DOOR IS CLOSED SHALL HAVE NON-REMOVABLE HINGE PINS. IN ADDITION, THEY SHALL HAVE 1/4" MINIMUM DIAMETERS STEEL JAMB STUDS WITH 1/4" MINIMUM PROJECTION, UNLESS THE HINGES ARE SHAPED TO PREVENT DOOR REMOVAL IF HINGE PINS ARE REMOVED.

STRIKE PLATES FOR LATCHES AND HOLDING DEVICES FOR PROJECTING DEAD BOLTS IN WOOD CONSTRUCTION SHALL BE SECURED TO THE JAMB AND WALL FRAMING WITH SCREWS NOT LESS THAN 2-1/2" IN LENGTH.

DEAD BOLTS SHALL CONTAIN HARDENED INSERTS.

STRAIGHT DEAD BOLTS SHALL HAVE A MINIMUM THROW OF 1" AND AN EMBEDMENT OF NOT LESS THAN 5/8"

HOOK SHAPED OR EXPANDING LAG DEAD BOLTS SHALL HAVE A MINIMUM THROW OF 3/4"

CYLINDER GUARDS SHALL BE INSTALLED ON ALL CYLINDER LOCKS WHENEVER THE CYLINDER PROJECTS BEYOND THE FACE OF THE DOOR OR IS OTHERWISE ACCESSIBLE TO GRIPPING TOOLS.

HARDWARE NOTES: REFERENCE HARDWARE SCHEDULE FOR SPECIFICATIONS.

KEYING: ALL CYLINDERS SHALL BE REMOVABLE CORE, MASTER KEYED TO INSTA-KEY SYSTEM. REFER DOOR HARDWARE SCHEDULE

FASTENERS:
PROVIDE ALL HARDWARE WITH ALL NECESSARY SCREWS, AND OTHER FASTENERS OF SUITABLE SIZE AND TYPE TO ANCHOR THE HARDWARE IN POSITION FOR LONG LIFE UNDER HARD USE.

FURNISH ITEMS COMPLETE WITH EXPANSION SHIELDS, TOGGLE BOLTS AND OTHER ANCHORS, IN ACCORDANCE WITH THE MATERIAL TO WHICH THE HARDWARE IS TO BE APPLIED AND THE RECOMMENDATIONS OF THE HARDWARE MANUFACTURER.
FASTENER FINISH SHALL HARMONIZE WITH THE HARDWARE MATERIAL. INSTALL HARDWARE ITEMS IN ACCORDANCE WITH THE SCHEDULE INCLUDED ON THE DRAWINGS, EXCEPT AS SPECIFICALLY REQUIRED TO COMPLY WITH LOCAL CODES AND AS RECOMMENDED BY THE DOOR AND HARDWARE INSTITUTE.

INSTALL HARDWARE IN COMPLIANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS. SET UNITS LEVEL, PLUMB AND TRUE. ADJUST AND CHECK OPERATION OF EVERY UNIT. REPLACE UNITS WHICH CANNOT BE ADJUSTED TO OPERATE FREELY AND SMOOTHLY.

COORDINATE WITH OTHER TRADES TO ASSURE PROPER AND ADEQUATE PROVISION IN THE WORK OF THOSE TRADES FOR INTERFACE WITH THE WORK OF THIS SECTION.

5. INSULATING GLASS UNIT

TEMPERED GLASS SHALL CONFORM WITH CPSC, ANSI, Z97.1, ASTM, FGMA STANDARDS

ENERGY CODE DATA FOR GLASS:
REFERENCE WINDOW SCHEDULE FOR SPECIFICATION.

6. GLAZING

ALL GLAZING SHALL CONFORM TO CONSUMER PRODUCT SAFETY STANDARD 16 CFR, PART 1201.

ALUMINUM STOREFRONT SYSTEM: THE SYSTEM SHALL BE AS NOTED ON THE DRAWINGS AS MANUFACTURED BY: KAWNEER COMPANY, INC., NORTHRUP ARCHITECTURAL SYSTEM.

STORE FRONT SHALL BE STRUCTURALLY REINFORCED, EXTRUDED ALUMINUM FRAMING COMPLETE WITH GLASS, NON-STRETCH HIGH SHORE VINYL AND ANCHORAGE ATTACHMENTS AND SHIMS REQUIRED TO SECURE WINDOW WALLS TO BUILDING STRUCTURAL SYSTEM.

FRAMES: SIZES AS SHOWN ON THE DRAWINGS, COMMERCIAL QUALITY EXTRUDED ALUMINUM (ASTM B221), COMPLETE WITH MATCHING PROFILE STOPS TO SUIT FRAMES AND OF ADEQUATE SIZE TO PROVIDE SUFFICIENT BITE ON GLASS, AND DRILLED HOLES, DEFLECTOR PLATES AND INTERNAL FLASHING TO ACCOMMODATE INTERNAL WEEP AND DRAINAGE SYSTEM.

REFER TO WINDOW SCHEDULE FOR ANODIZED ALUMINUM FINISH COLOR.

7. DRIVE-THRU WINDOW

PASS THROUGH WINDOW AT DRIVE-THRU WITH LOCK, PRE-GLAZED WITH ALUMINUM FRAME. SEE WINDOW SCHEDULE ON ELEVATION SHEETS FOR MANUFACTURERS AND DETAILED SPECS.

PANDA EXPRESS CHINESE KITCHEN

PANDA RESTAURANT GROUP INC.
1683 Walnut Grove Ave.
Rosemead, California
91770
Telephone: 626.799.9898
Facsimile: 626.372.8288

All ideas, designs, arrangement and plans indicated or represented by this drawing are the property of Panda Express Inc. and were created for use on this specific project. None of these ideas, designs, arrangements or plans may be used by or disclosed to any person, firm, or corporation without the written permission of Panda Express Inc.

REVISIONS:

ISSUE DATE:

1st	ISSUE FOR BID & PERMIT	01-11-17

DRAWN BY: RR

PANDA PROJECT #: S8-17-D5197
ARCH PROJECT #: 1701

RANDY REYNOLDS ARCHITECT
1702 MILDARE COURT ▯ THOMPSONS STATION, TN 37179
PHONE (615) 591-0675 ▯ FAX (866) 584-1225

PANDA EXPRESS
HIGHWAY 90 AT SHADOW OAK DRIVE
4890 HIGHWAY 90
PACE (MILTON), FL 32571
2200 TRUE WARM & WELCOME

G-003

SPECIFICATIONS